



# 6100 Center Drive

6100 Center Drive  
Los Angeles, California, 90045



## Available ISPs

Carrier	Cable Type	Network Type	Cable Distribution
AT&T	Fiber	Type 1	Full Coverage
AT&T	Copper	Phone or Cable	Full Coverage
Cogent	Fiber	Type 2	Full Coverage
Verizon Enterprise	Fiber	Type 1	Direct to Tenant
XO Communications	Fiber	Type 1	Direct to Tenant
Zayo Group	Fiber	Type 1	Direct to Tenant

## Key Features of Connectivity

- 5 fiber providers can provide dedicated, business grade internet access with guaranteed upload and download speeds.
- Additional riser capacity is available to support future needs of tenants and ISP's throughout the entire building.
- Telecom equipment is kept in a protected space, separate from other utilities reducing the potential for service disruption.
- Public Wi-Fi is provided for free by building management in common areas.
- Telecom equipment is located above grade to prevent against damage from flooding.
- Dedicated risers are present to contain and protect telecom cables from risk of damage.

# Wired Certification Fact Sheet Explainer

Cabling Type	Use	Maximum Speed (Bandwidth rates)
Copper	Used in older Digital Subscriber Line (DSL) networks, these networks use copper telephone lines to provide Internet access to customers.	40 Mbps Down 5 Mbps Up
Coaxial	Used in most Cable provider networks. Typically used for Television sets or Modems.	300 Mbps Down 30 Mbps Up
Fixed Wireless	Rooftop based antenna networks are used for both primary and secondary forms of connectivity. Top choice for redundant connection because it doesn't rely on existing wireline cabling into a building. Fixed Wireless should not be confused with Satellite Dishes which provide Television service and minimal Internet capabilities.	1000 Mbps (1 Gig) Up and Down
Fiber	Most technologically advanced form of cabling used in buildings. Signals can travel for greater distances at faster speeds.	10,000 Mbps (10 Gig) Up and Down

Distribution Type	Definition
Direct to Tenant Space Only	Carrier runs a single cable from where their equipment is located to the tenant they are servicing. This is not ideal for a tenant ordering new service as it could require extensive construction which will delay the tenant getting timely service.
Partial Distribution	Partial Distribution is defined as a distribution point every 6-10 floors. Carrier places several distribution points within the building where they can connect additional cables for tenants. A distribution point can either be a termination box or a coil of spare cabling. For new service requests, partial distribution is less time intensive than direct to tenant space cables.
Full Distribution	Carrier places distribution points (a termination box or a coil of spare cabling) every 5 floors or less and can easily serve any tenant in the building. This setup drastically reduces the time it takes for tenants to receive new service.

Network Type	Definition
Type 1	Carrier owns the fiber entering the building.
Type 2	Carrier is using someone else's fiber, copper or coax to reach a tenant.
Phone Company or Cable Network	Carrier is entering the building with Copper Phone Cables or Coaxial Cables. These usually only offer slower Internet speeds.
Rooftop Connection	Rooftop connections are designated for Fixed Wireless providers. See definition above.